Items of work.		*Per.*	*Quantity.*
	Left bank channel.		
Earthwork excavation	... ...	C. yds.	4,872
Gravelly soil do	... ...	,,	5,718
Soft rock do	... ...	,,	1,397
Hard rock do	... ...	,,	1,253
Earthwork embankment	... ...	,,	4,615
Mile stones	... ...	No.	5
Bed grade stones	... ...	,,	68
Index stones	... ...	,,	68
Bank grade stones	... ...	,,	64
	Aqueduct in mile $\frac{3}{4}$ across Kodihalla of Rajimakalhalli Katte.		
Earthwork	... ...	C yds.	51
Burnt brick in surki mortar	... ...	C. ft.	2,730
Burnt stone slabs 6" thick	... ...	S. ft.	499
Do 4" thick	... ...	,,	84
Concrete flooring	... ...	C. ft.	65
Plastering with surki mortar	... ...	Sqrs.	13·48
Rough stone revetment	... ...	C. yds.	93
	Masonry drop in $\frac{3}{5}$.		
Earthwork	... ...	C. yds.	9
Benching rock	... ...	S. ft.	66
Burnt brick in surki mortar	... ...	C. ft.	160
Burnt stone slabs 6" thick	... ...	S. ft.	30
Plastering with surki mortar	... ...	Sqrs.	·67
	Masonry drop in mile $\frac{3}{5}$.		
Earthwork	... ...	C. yds.	23
Benching rock	... ...	S. ft.	86
Burnt brick in surki mortar	... ...	C. ft.	326
Stone slabs 6" thick	... ...	S. ft.	28
Plastering with surki mortar	... ...	Sqrs.	·77
	Relieving weir in mile $\frac{7}{8}$ across the Kodihalla of Kondahalli Katte.		
Earthwork	... ...	L. S.	
Burnt brick in surki mortar	... ...	C. ft.	437
Burnt stone slabs 6" thick	... ...	S. ft.	154
Plastering with surki mortar	... ...	Sqrs.	2·14
Wooden shutter with lifting rings, etc.	... ...	L. S.	
Madaboys	... ...	No.	12
Relieving weir	... ...	,,	8

V. AIYASWAMI IYER,
Executive Engineer.

SHIMOGA DIVISION.

Dated 16th August 1913.

Notice is hereby given to the public that an amount of Rs. 3-14-6 due to Ananta Rao for the work done by him in the annual repairs of Honnali-Basavapatna road, lies unclaimed in the Executive Engineer's office at Shimoga.

If the said amount is not claimed before three months from this date either by Ananta Rao or his legal heirs, the amount will be credited to Government as unclaimed property.

V. R. NIJAGAL,
Executive Engineer.

Notice dated Camp Mysore, 26th August 1913.

The tongas and victorias will be withdrawn from hire from the 1st September 1913. till the end of November next.

A. JONES, LT.-COL.,
Officiating Military Secretary.